



## Project:

Kuala Lumpur Metro, MRT Underground Station

## System:

Nukote ST (Pure Polyurea)

Nukote HLT

Nukote EP Prime II

## Description:

The project specified the application of Nukote ST (Pure Polyurea) over newly poured concrete. The client's construction schedule required immediate coating after casting. Nukote HLT followed by Nukote EP Prime II was applied to eliminate vapor entrapment and the potential of pin-holing of the finished surface. The completed coated area was buried within 24 hours after coating application was completed.

**Client:**  
NMRT Corporation

**Distributor:**  
Nukote Industries  
Malaysia

**Consultant:**  
AECOM

**Contractor:**  
MMC-GAMUDA KVMRT  
(T) SDN BHD

**Applicator:**  
Nukote Industries  
Malaysia

**Area:**  
Total 200,000 m<sup>2</sup>  
Each Phase 10,000 m<sup>2</sup>

**Location:**  
KL Sentral/Malaysia